

APPLICATION AND PERMIT FOR INDIVIDUAL SEWAGE DISPOSAL SYSTEM



LARIMER COUNTY
DEPARTMENT OF HEALTH & ENVIRONMENT
1525 BLUE SPRUCE DRIVE
FORT COLLINS, COLORADO 80524

1. 1/4 S 23 T 07 R 70 Parcel # 07230-00-031 (970) 498-6775 F.C.
2. Subdivision Redstone Canyon (970) 577-2050 E.P.
3. Lot 37 Block Filing Tract (970) 498-6772 FAX
4. New System ☒ Repair Remodel Vault/Privy
5. Business Name
6. Addr/Loc 13804 NCR 25E, Loveland, CO 80538
7. Owner TAYLOR, PETER Phone
8. Address 504 SMITH ST FORT COLLINS CO 80538
9. Agent BLACKMER, ALEX Phone (970) 204-1275 204-020
10. Address 14285 N CTY RD 25 E LOVELAND CO 80538
11. Contractor Phone
12. Address
13. Engineer Signature Date
14. Build type SF W/LP Bsmt Bath Walk Out Capacity 3 BDR Lot Size 40A
15. Well Y Water Dist. Sanit. Dist.
16. Plot Plan ☒ Eng. Report ☒ Engineer's Design LANDMARK
17. Owner/Agent Signature [Signature] Date 06/29/1998
Fee \$ 350.00 Receipt # 10138789 BP # 98-15751A Cross Ref #

Permission is hereby granted to the owner or his agent to perform the work indicated below in accordance with the Larimer County Individual Sewage Disposal Regulations and is conditional upon the final installation approval of the Larimer County Department of Health and Environment. This permit is to remain in full force for the duration of the Larimer County Building Permit, or 120 days after its issuance, where applicable, providing it is not revoked for noncompliance. The issuance of this permit does not constitute assumption by the Department or its employees of liability for the failure or inadequacy of the sewage disposal system.

18. Depth to Water Table 8' Perc Rate 56 gpm Depth to bedrock 8' Slope _____

19. Type and Design of System Install minimum 1000 gallon septic tank with 1263 sq ft of absorption bed or 49 units of infiltrator bed. Maintain All lines 1 ft depth of backfill. Make positive drainage around the field area. 100 ft from well, 10 ft property, 20 ft from house

20. Maintenance Schedule Pump tank every 3 yrs.
21. Please notify the department 48 hours in advance of backfilling to obtain final inspection for issuance of "Occupancy Certificate".

Approval Signature	Date	Approval Signature	Date
22. Preliminary: <u>Sue S</u>	<u>7-6-98</u>	24. Construction Inspection _____	_____
23. Site Inspection: <u>Sue S</u>	<u>7-6-98</u>	25. Final inspection _____	_____
		26. Occupancy Permit Ok'd _____	_____

Route: White - Owner; Pink - System Contractor; Tag Copy - File.

L.C.D.H.E. 233 (8/96)